



**Atacama  
Large  
Millimeter  
Array**

**APP Optical Fiber Link system  
prototype test report**

ALMA-05.11.40.03-0002-A-REP

Version: A  
Status: Draft  
2013-04-24

<b>Prepared By:</b>	<b>Organization</b>	<b>Signature and Date</b>
Mareki Honma	National Astronomical Observatory of Japan	
<b>Approvals:</b>		
TBD		
<b>Release:</b>		
TBD		



**ALMA Project  
APP  
Optical Fiber Link system  
prototype test report**

Doc #: ALMA-05.11.40.03-0002-A-REP  
Date: 2013-04-24  
Status: Draft  
(Draft, Pending, Approved, Released, Superseded, Obsolete)  
Page: 2 of 11

### Change Record

Version	Date	Affected Section(s)	Change Request #	Reason/Initiation/Remarks
A	2013-04-24	ALL	None	First Issue



**ALMA Project  
APP  
Optical Fiber Link system  
prototype test report**

Doc #: ALMA-05.11.40.03-0002-A-REP  
Date: 2013-04-24  
Status: Draft  
(Draft, Pending, Approved, Released, Superseded, Obsolete)  
Page: 3 of 11

## Contents

<b>1</b>	<b>Introduction.....</b>	<b>5</b>
1.1	Purpose.....	5
1.2	Reference Documents .....	5
1.3	Abbreviations and Acronyms .....	5
<b>2</b>	<b>Prototype production.....</b>	<b>5</b>
<b>3</b>	<b>Prototype test.....</b>	<b>7</b>
3.1	Full-data-rate transmission test.....	7
3.2	Attenuation tolerance test .....	8
3.3	Long-term running test .....	9
3.4	Power consumption.....	9
3.5	Acceptable input voltage.....	9
3.6	Power supply.....	9
3.7	Cooling capability .....	10
3.8	Software interface test.....	10



**ALMA Project  
APP  
Optical Fiber Link system  
prototype test report**

Doc #: ALMA-05.11.40.03-0002-A-REP  
Date: 2013-04-24  
Status: Draft  
*(Draft, Pending, Approved, Released, Superseded, Obsolete)*  
Page: 4 of 11

**List of Figures**

Figure 1: Front view of XW-100 ..... 6  
Figure 2: Rear view of XW-100 ..... 6  
Figure 3: Schematic diagram for data transmission test at the full rate..... 7  
Figure 4: Picture of the two sets of XW-100 under testing ..... 8  
Figure 5: Example result of attenuation tolerance test..... 9  
Figure 6: Screen shot of telnet /VSI-S connection to the OFL system..... 11



**ALMA Project  
APP  
Optical Fiber Link system  
prototype test report**

Doc #: ALMA-05.11.40.03-0002-A-REP  
Date: 2013-04-24  
Status: Draft  
(Draft, Pending, Approved, Released, Superseded, Obsolete)  
Page: 5 of 11

## **1 Introduction**

### **1.1 Purpose**

This document describes the details of prototype production and test results of the OFL system prototype.

### **1.2 Reference Documents**

[RD 1] ALMA Phasing Project Plan  
[RD 2] APP Optical Fiber Link system design

### **1.3 Abbreviations and Acronyms**

<b>APP</b>	ALMA Phasing Project
<b>AOS</b>	Array Operations Site
<b>DWDM</b>	Dense Wavelength Division Multiplexing
<b>OFL</b>	Optical Fiber Link
<b>OSF</b>	Operations Support Facility
<b>NAOJ</b>	National Astronomical Observatory of Japan
<b>VLBI</b>	Very Long Baseline Interferometry
<b>VSI</b>	VLBI Standard Interface

## **2 Prototype production**

The purpose of the OFL system is to transmit the antenna sum data from the AOS to the OSF while using minimal fiber resources [RD01]. Based on the detailed design is summarized in the OFL system design document [RD02], prototype production was conducted in early 2013. Prototype manufacturer and model number are:

**Manufacturer:** Elecs Engineering

**Model Number:** XW-100 (both the Multiplexer and Demultiplexer)

Front and rear views of XW-100 are shown below. Nine slots on the front panel are attached with 10GBASE-SR XFP modules to constitute nine local ports including one spare. The DWDM remote port is located at the bottom-right corner of the front panel. On the rear panel, three cooling fans are attached. The power on-off switch is located at the bottom-left corner on the rear.



**ALMA Project  
APP  
Optical Fiber Link system  
prototype test report**


Doc #: ALMA-05.11.40.03-0002-A-REP  
Date: 2013-04-24  
Status: Draft  
(Draft, Pending, Approved, Released, Superseded, Obsolete)  
Page: 6 of 11



**Figure 1: Front view of XW-100**



**Figure 2: Rear view of XW-100**

	<p><b>ALMA Project</b>  <b>APP</b>  <b>Optical Fiber Link system</b>  <b>prototype test report</b></p>	<p>Doc #: ALMA-05.11.40.03-0002-A-REP  Date: 2013-04-24  Status: Draft  (Draft, Pending, Approved, Released, Superseded, Obsolete)  Page: 7 of 11</p>
---	--	---

### 3 Prototype test


In order to evaluate the performance the OFL system prototype XW-100, we have conducted various tests at the manufacturer as well as at NAOJ Mitaka, and below we report details of the test results.

#### 3.1 Full-data-rate transmission test

**Specification:** The OFL system has to be capable of sending data at a total rate of  $8 \text{ Gbps} \times 8 = 64 \text{ Gbps}$ .

**Test description:** The test data from a 10GbE analyzer was sent to OFL system in a daisy chain mode so that one 10GbE stream is copied to all the nine ports (including the spare port) of Multiplexer and sent to Demultiplexer through a single fiber at the same time with DWDM technique. See figure 1 for the experiment setup. Note that an optical attenuator was inserted to emulate the fiber loss between AOS and OSF.

**Result:** Maximum data rate of  $9.8 \text{ Gbps} \times 9 (=88.2 \text{ Gbps})$  was achieved without any packet loss or any other error. Note that 9.8 Gbps is the maximum throughput of one 10GbE stream, and so XW-100 achieved the maximum transmission rate based on 10GbE.



**Figure 3:** Schematic diagram for data transmission test at the full rate



**ALMA Project  
APP  
Optical Fiber Link system  
prototype test report**

Doc #: ALMA-05.11.40.03-0002-A-REP  
Date: 2013-04-24  
Status: Draft  
(Draft, Pending, Approved, Released, Superseded, Obsolete)  
Page: 8 of 11



**Figure 4:** Picture of the two sets of XW-100 under testing


### **3.2 Attenuation tolerance test**

**Specification:** The optical fiber between AOS and OSF has an optical attenuation of about 7.5 dB. The OFL has to be able to establish a link between AOS and OSF with this attenuation.

**Test description:** An optical attenuator is inserted in the DWDMed stream between the Multiplexer and Demultiplexer, and attenuation tolerance level is measured.


**Result:** It is confirmed that the data can be correctly transmitted with an attenuation level less than 20 dB. Figure 5 shows an example of error rate measured against the attenuation level.





**ALMA Project  
APP  
Optical Fiber Link system  
prototype test report**

Doc #: ALMA-05.11.40.03-0002-A-REP  
Date: 2013-04-24  
Status: Draft  
(Draft, Pending, Approved, Released, Superseded, Obsolete)  
Page: 9 of 11



**Figure 5:** Example result of attenuation tolerance test

### 3.3 Long-term running test

**Specification:** The OFL system can be operated without any significant trouble for a period longer than normal VLBI observations (at least ~10 hours).

**Test description:** Long-term running test of the OFL system was conducted at the full data rate.

**Result:** No packet loss or data error occurred through the test run for three weeks.

### 3.4 Power consumption

**Specification:** Power consumption is less than 150 W.

**Result:** Power consumption in regular operation is measured to be ~68 W.

### 3.5 Acceptable input voltage

**Specification:** Input AC voltage of 100/230 V must be accepted.

**Result:** Operation is confirmed with input AC voltages of 90, 100, 110, 200, 230, 240 V.

### 3.6 Power supply

**Specification:** Operation with one power supply unit is possible.

**Result:** Operation with one power supply unit is confirmed.



**ALMA Project  
APP  
Optical Fiber Link system  
prototype test report**

Doc #: ALMA-05.11.40.03-0002-A-REP  
Date: 2013-04-24  
Status: Draft  
(Draft, Pending, Approved, Released, Superseded, Obsolete)  
Page: 10 of 11

### 3.7 Cooling capability

**Specification:** The OFL system must have cooling capability enough for operation at the high site. Cooling with two fans (out of the three fans attached) should be OK for redundancy.

**Test description:** Surface temperature of XFP module was measured with varying the number of fans in operation (decreasing from three to one). The experiments were done under room temperature and sea-level atmospheric pressure. Temperature increase with respect to the outside air temperature was measured as a function of the number of fans in operation.

**Result:** The temperature increase is summarized below. Maximum temperature increase was 9.5 C deg in case of one fan in operation. This corresponds to the XFP module surface temperature of ~35 C deg (using the room temperature of ~25 C deg), which is far below the maximum operation temperature of 75 C deg. Note that at the high site (AOS) the air density is roughly half of the sea-level atmosphere, and thus operation with one fan at the sea level roughly emulates operation with two fans at the high site.

Number of fans in use	Temperature increase <sup>1)</sup>	note
3	2.5 C deg	
2	5 C deg	
1	9 C deg	Roughly corresponds to operation with two fans at AOS

1) Surface temperature increase of XFP module with respect to the room temperature

### 3.8 Software interface test

**Specification:** The OFL system is connected through LAN with telnet / VSI-S protocol.

**Result:** Connection with telnet / VSI-S is confirmed. Commands are properly sent to Multiplexer and Demultiplexer and also statuses are properly returned from Multiplexer and Demultiplexer. Figure 6 is a screen shot of the software interface test.



**ALMA Project**  
**APP**  
**Optical Fiber Link system**  
**prototype test report**

Doc #: ALMA-05.11.40.03-0002-A-REP  
Date: 2013-04-24  
Status: Draft  
(Draft, Pending, Approved, Released, Superseded, Obsolete)  
Page: 11 of 11

```
192.168.2.110 - PuTTY
!;!!=7;
!;!!=7;
!;!!=7;
set_alarmmask?;!set_alarmmask?0:000000000;
show_alarm_hex?;!show_alarm_hex?0:23:00000000:00000000:00000000:01ff01ff;
show_alarm_str?;!show_alarm_str?1:Temperature 23;
!show_alarm_str?1:The XFP module of the 10G ZR port9 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G ZR port8 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G ZR port7 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G ZR port6 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G ZR port5 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G ZR port4 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G ZR port3 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G ZR port2 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G ZR port1 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G local port9 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G local port8 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G local port7 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G local port6 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G local port5 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G local port4 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G local port3 detects receiver loss of signal;
!show_alarm_str?1:The XFP module of the 10G local port2 detects receiver loss of signal;
!show_alarm_str?0:The XFP module of the 10G local port1 detects receiver loss of signal;
show_system?;!show_system?0:Ver.1.0.0:2013/04/03 10:55:43;
```

**Figure 6:** Screen shot of telnet /VSI-S connection to the OFL system.